



RIPARIAN SEED MIX 2. SEED AT A RATE OF 20.0 kg/ha. 3. SPECIES INCLUDED AND APPROXIMATE VOLUME OF THE TOTAL 30% FOWL BLUEGRASS (Poa palustris) 30% FOX SEDGE (Carex vulpinoidea)


8% PATH RUSH (Juncus tenuis)

EROSION CONTROL AT A RATE OF 30 kg/ha.

30% VIRGINIA WILD RYE (Elymus virginicus) 4. SIMULTANEOUSLY SOW COVER CROP OF ANNUAL OATS FOR









GENERAL NOTES

- 1. MEASUREMENTS IN METRES AND/OR MILLIMETRES UNLESS OTHERWISE SHOWN.
- 2. CONSTRUCTION ACCESS WILL BE AS SHOWN ON OPS-1, OPS-2, AND OPS-3 PLANS 3. THE PROJECT LEADER IS RESPONSIBLE FOR ENSURING THAT THE EROSION CONTROLS ARE MAINTAINED &
- OPERATING AS INTENDED, INCLUDING MAKING FIELD ADJUSTMENTS AS NECESSARY, TO THE SATISFACTION OF THE TOWN OF RICHMOND HILL TO ENSURE ADEQUATE EROSION PROTECTION.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION, MAINTENANCE AND REMOVAL OF ALL TEMPORARY CONSTRUCTION. AS DIRECTED BY THE ENGINEER.
- 5. THE LOCATION OF EROSION AND SEDIMENT CONTROL DETAILS ARE SHOWN SCHEMATICALLY
- 7. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED AND SHALL BE DETERMINED
- AS NECESSARY BY SITE CONDITIONS. 8. SERVICING OF CONSTRUCTION EQUIPMENT ON SITE IN DESIGNATED AREAS ONLY

GOOD HOUSEKEEPING AND MAINTENANCE MEASURES

- 1. NO CONSTRUCTION ACTIVITY OR MACHINERY SHALL GO BEYOND THE SILT/SNOW FENCE OR LIMITS. ALL VEHICLES SHALL LEAVE THE SITE AT DESIGNATED LOCATIONS AS SHOWN ON THE
- 2. CLEANING OF EXISTING ROAD(S) AT SITE ACCESS POINT SHALL BE DONE AS NECESSARY THROUGH REGULAR INSPECTION OR AS DIRECTED BY THE TOWN.
- 3. STOCKPILES TO BE SEEDED IMMEDIATELY UPON COMPLETION TO STABILIZE AGAINST
- 4. CLEANING AND REPAIRS OF CHECK DAMS, MUD MATS AND ANY OTHER TEMPORARY SEDIMENT CONTROL MEASURES SHALL BE DONE PRIOR TO EVERY STORM EVENT THROUGH
- 5. SEDIMENT/SILT SHALL BE REMOVED FROM THE SEDIMENT CONTROL DEVICES, AFTER STORM EVENTS AND DISPOSED OF IN AREAS AS APPROVED BY THE ENGINEER.
- DUST CONTROL TO BE REVIEWED DAILY. WATER TRUCK TO BE PROVIDED ON-SITE AND ALL HAUL ROADS/WORKNG AREAS TO BE SPRAYED WITH WATER AS REQUIRED TO ENSURE DUST IS CONTROLLED ON-SITE.
- 7. IN ADDITION WHILE THE FACILITY IS OPERATIONAL, SWEEPING AND FLUSHING WILL TAKE PLACE AS NEEDED PER THE FOLLOWING:
- a. FRIDAY EVENINGS AFTER LAST TRUCK HAS LEFT THE SITE;
- AFTER SIGNIFICANT RAINFALL EVENTS, UNTIL INTERNAL HAUL ROADS HAVE DRIED
- AFTER RECEIVING NOTIFICATIONS FROM THE TOWN OR REGION OF COMPLAINTS OF EXCESSIVE MUD FROM THIS SITE. COMPLAINTS RECEIVED OUTSIDE OF OPERATIONAL HOURS WILL BE ASSESSED AND ACTIONS APPLICABLE TO THE SITE COMPLETED ONCE
- 8. ALL LITTER AND DEBRIS SHALL BE MONITORED AND DISPOSED OF DAILY OR AS NECESSARY
- THROUGH REGULAR INSPECTION. 9. TEMPORARY SEDIMENT PONDS TO BE INSPECTED AFTER STORM EVENTS AND CLEANED OF
- SEDIMENT EVERY SIX (6) MONTHS (MINIMUM). . 10. THE VEHICLE TRACKING PAD(S)/MUD MAT(S) MUST BE INSTALLED AT THE SITE ACCESS
- BEFORE ACTIVITIES BEGIN IN ORDER TO PREVENT MUD TRACKING ONTO ADJACENT ROADS.
- 11. TEMPORARY SWALES TO TEMPORARY SEDIMENT CONTROL PONDS TO BE STABILIZED PRIOR






Drawing Revisions

Note: * indicates signatures on original issue of drawing or last revision of drawing

Conditions of Use. This document may only be used by GHD's client (and any other person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.





140 Allstate Parkway, Suite 210 Markham Ontario L3R 5Y8 **T** 1 905 752 4300 **F** 1 905 752 4301 **E** ytomail@ghd.com **W** www.ghd.com

Client RICE GROUP PTY LTD

Project MCCOWAN & MILL ROAD


Title NOTES AND DETAILS

Scale	1:1000	DO NOT SCALE
Drawn	L. LI	
Designer	L. LI	
Drafting Check	L .LI	
Design Check	A. EMER	
Approved (Project Director) A. EMER		
Date	DEC 2018	


This Drawing must not be used for Construction unless signed as Approved

DET-1


Original Size Arch D




4079








Tree #	Common Name	Scientific Name	DBH (cm)	Proposed Removal (x)
47	Scots pine	Pinus sylvestris	21	
61	Scots pine	Pinus sylvestris	20	
62	Scots pine	Pinus sylvestris	32	
63	Scots pine	Pinus sylvestris	30	
64	Scots pine	Pinus sylvestris	28	
65	Scots pine	Pinus sylvestris	28	
66	Manitoba maple	Acer negundo	21.0	
67	Manitoba maple	Acer negundo	23.5	
68	Manitoba maple	Acer negundo	70, 44.5	
69	Manitoba maple	Acer negundo	20.5	
70	Manitoba maple	Acer negundo	24.0	
72	Manitoba maple	Acer negundo	20, 20, 21, 15.5, 14, 16	
73	Manitoba maple	Acer negundo	20.5	х
74	Manitoba maple	Acer negundo	22.0	
75	Manitoba maple	Acer negundo	28.0	
76	Manitoba maple	Acer negundo	24.5	
77	Manitoba maple	Acer negundo	16, 20.5	
78	Manitoba maple	Acer negundo	24, 14, 20, 26	
79	Manitoba maple	Acer negundo	22, 22.5, 19, 20, 22.5	
80	Manitoba maple	Acer negundo	45, 35	
81	Manitoba maple	Acer negundo	22	
83	Manitoba maple	Acer negundo	50, 14.5	
84	Manitoba maple	Acer negundo	69	
85	Manitoba maple	Acer negundo	31	
86	Manitoba maple	Acer negundo	42.0	
87	Manitoba maple	Acer negundo	44.0	
88	Manitoba maple	Acer negundo	42.5	
89	Manitoba maple	Acer negundo	71.0	
90	Manitoba maple	Acer negundo	22.5, 22, 13	
91	Manitoba maple	Acer negundo	40.0	
92	Manitoba maple	Acer negundo	37, 36	
93	Manitoba maple	Acer negundo	55, 32	
94	Manitoba maple	Acer negundo	44.5	
95	Manitoba maple	Acer negundo	37, 24	
96	Manitoba maple	Acer negundo	21, 5, 7, 7, 10, 10	
97	Manitoba maple	Acer negundo	33, 30.05, 31	
98	Manitoba maple	Acer negundo	26, 17.5	
99	Manitoba maple	Acer negundo	25.5	
100	Manitoba maple	Acer negundo	43, 39.5	Potential removal
				Retain, as possible
1389	European mountain-ash	Sorbus aucuparia	24	



Plot Date: 12 December 2018 - 4:45 PM Plotted by: Jonathan Compton

TREE INVENTORY TABLE OF SELECT TREES





TREE PROTECTION NOTES

FENCE MATERIAL:

- PLASTIC ORANGE FENCING (120 GM TALL) SHALL BE USED OR EDUIVELANT AS APPROVED BY YORK REGION AND INSTALLED WITH WIRE TIES ON METAL T- DO NOT STORE MATERIALS OR EQUIPMENT IN THE
- BAR POSTS (186 CM TALL) SPACED2500mm4PART FENCE MAY BE COMBINED WITH SILT FENCING

FENCE LOCATION: INSTALL FENCE AS PER TREE PROTECTION

- DETAIL FOR INDIVIDUAL TREES, FENCE IS TO BE INSTALLED AT THE LIMITS OF CONSTRUCTION OR AT THE DRIPLINE OF THE TREE, WHICHEVER IS FURTHER FROM THE TREE. FENCE CAN BE LOCATED CLOSER TO THE TRUNK ONLY WITH AUTHORIZATION FROM YORK REGION
- FOR ROWS OF TREES, SUCH AS FOUND IN BOULEVARDS, A SINGLE LINEAR FENCE SHOULD BE INSTALLED WHICH FOLLOWS THE LIMITS OF THE CONSTRUCTION ZONE
- SIGNAGE:

 INSTALL TREE PROTECTION SIGN ON FENCE FACING CONSTRUCTION ZONE AT 100 METER INTERVALS AS PER NHFS-04 TREE PROTECTION DETAIL

PRUNING:

 ALL ROOTS WHICH ARE EXPOSED THROUGH EXCAVATION ARE TO BE PRUNED BACK TO THE BOIL

 BRANCHES DAMAGED OR INTERFERING WITH CONSTRUCTION ACTIVITIES ARE TO BE PRUNED BY AN INTERNATIONAL BOCKETY OF ARBORICULTURE (ISA) CERTIFIED ARBORIST

FENCE MAINTENANCE:

MAINTAIN FENCE IN WORKING CONDITION AT ALL.

- DO NOT MOVE FENCE WITHOUT PRIOR AUTHORIZATION FROM YORK REGION

MONITORING:

PROTECTED AREA

 CONDUCT WEEKLY MONITORING OF FENCE AND TREE HEALTH THROUGHOUT THE DURATION OF THE CONSTRUCTION PROJECT OR ACCORDING TO A SCHEDULE NOTED IN AN APPROVED TREE PRESERVATION PLAN.

ARBORICULTURAL PRINCIPLES AND BEST MANAGEMENT 3. ALL TREE PROTECTION FENCE TO BE IN ACCORDANCE WITH DETAIL 2 (TREE PROTECTION DETAIL) AND DETAIL

ADJACENT TREE REMOVAL ACTIVITIES TO BE PRUNED BY COMPETENT ARBORISTS IN ACCORDANCE WITH CURRENT

3 (TREE PROTECTION NOTES AND SIGN DETAIL). 4. TREE PROTECTION MEASURES TO BE LEFT IN PLACE AND MAINTAINED FOR THE DURATION OF CONSTRUCTION ACTIVITIES. TREE PROTECTION FENCE SHOULD BE INSPECTED ON A WEEKLY BASIS FOR THE DURATION OF

1. ALL WOOD CHIPS/BRUSHWOOD FROM REMOVED SITE

TREES TO BE REMOVED FROM SITE OR PLACED AS

2. TREE BRANCHES DAMAGED DURING CONSTRUCTION OR

TREE REMOVAL AND TREE PROTECTION NOTES:

DIRECTED BY THE OWNER/ENGINEER.


OWNER/ENGINEER. 5. TREE PROTECTION MEASURES TO BE REPAIRED AND/OR

TO BE REMOVED ONLY WHEN DIRECTED BY THE

REPLACED IMMEDIATELY WHEN DAMAGED. 6. ANY TREES NOT INVENTORIED ARE TO BE PROTECTED BY A MINIMUM 5 METRE OFF-SET FROM THE EDGE OF THE TREE CROWN (DRIPLINE). IF WORKS ARE NEEDED WITHIN 5 METRES OF A NON-INVENTORIED TREE, PROTECTION MEASURES WILL BE RECEIVED BY AN ARBORIST.

THE CONSTRUCTION PHASE. TREE PROTECTION MEASURE

7. NO EQUIPMENT, VEHICLES, OR MATERIAL SHALL BE PILED, PLACED. OR STORED IN TREE PROTECTION AREAS OR AREAS BEYOND TREE PROTECTION FENCE.




Drawing Revisions

Note: * indicates signatures on original issue of drawing or last revision of drawing Conditions of Use. This document may only be used by GHD's client (and any other

person who GHD has agreed can use this document) for the purpose for which it was prepared and must not be used by any other person or for any other purpose.







140 Allstate Parkway, Suite 210 Markham Ontario L3R 5Y8 T 1 905 752 4300 F 1 905 752 4301 **E** ytomail@ghd.com **W** www.ghd.com

Client RICE GROUP PTY LTD

Project MCCOWAN & MILL ROAD

Title DETAILS AND NOTES

Scale N.T.S.	DO NOT SCALE
Drawn	
Designer	
Drafting Check	
Design Check	
Approved (Project Director)	
Data	

This Drawing must not be used for Construction unless signed as Approved


TP-3

Drawing No.

FIRST SUBMISSION

Arch D Rev. A





Ocalc	1:1000	DO NOT SCALE
Drawn	L. LI	
Designer	L. LI	
Drafting Check	A. EMER	
Design Check	A. EMER	
Approved (Project Director) A. EMER		
Date	DEC 2018	