


# NOTES:


- 1. GROUND HYDRANT BY ZURN ENGINEER SOLUTIONS, MODEL NO. 2/390.
- 2. PROVIDE SHOP DRAWINGS.



# GROUND HYDRANT FOR WINTER USE


STANDARD	DETAIL
APPROVED COUNCIL	DWG. No.
REVISION No.	701
DATE 2009	

- ① QUICK COUPLER
- 2 LASCO SNAPLOCK WITH REBARS AND 25mm PVC SUPPORTS
- (3) SWING ASSEMBLY
- (4) MAINLINE FEEDS




# INSTALLATION NOTES:

- -QUICK COUPLER TO BE ON SWING ASSEMBLY
- -SUPPORT QUICK COUPLER WITH A LASCO SNAPLOCK
- -USE |2mm REBAR AND 25mm SCHEDULE 80 PVC (200mm LONG PER SIDE) WITH LASCO SNAPLOCK
- -DRILL HOLE FOR I" PVC THROUGH VALVE BOX
- -FILL BOTTOM OF VALVE BOX WITH 150mm OF 25mm GRAVEL
- -SUPPORT VALVE BOX WITH BLOCKS FOR EXPECTED TRAFFIC




# QUICK COUPLING TURF VALVE

STANDARD	DETAIL		
APPROVED COUNCIL	DWG. No.		
REVISION No.	702		
DATE 2009			




## NOTES:

- 1. VALVE CHAMBER EXCAVATION TO BE BACKFILLED WITH GRANULAR 'B'
- 2. CAP TO BE DRILLED FOR SLIPING ALE BOX TO BE SET AT GROUND LEVEL.
- 3. ALL PIPE PASSING THROUGH PRE-CAST CHAMBER WALLS TO BE SEALED WITH NON-SHRINKABLE MOTAR.
- 4. THE TOP OF VALVE BOXES AND CHAMBERS SHALL BE SET FLUSH WITH FINISH GRADE.
- 5. ALL WATER LINE SIZING TO BE CERTIFIED BY A CONSULTANT THAT THEY MEET ALL APPLICABLE CODES AND/OR LEGISLATION.
- 6. ALL ITEMS REFERENCED ARE TO BE CONFIRMED TO ALL CURRENT O.P.S.D. STANDARDS.




## VALVE CHAMBER


STANDARD	DETAIL
APPROVED COUNCIL	DWG. No.
REVISION No.	703
2009	



DATE 




## **BACKFLOW PREVENTOR FRONT ELEVATION**



#### BACKFLOW PREVENTOR SIDE ELEVATION

### NOTES:

- I. PROVIDE SHOP DRAWINGS FOR APPROVAL OF BACKFLOW PREVENTOR AND METER ASSEMBLY.
- 2. PROVIDE CONCRETE PAVING PAD 150 WIDER THAN CABINET DIMENSIONS.
- 3. LOCATION OF PAD MINIMUM 1000 FROM PROPERTY LINE OR AS PER DRAWING.
- 4. DRAIN AND COMPLETELY FLUSH SYSTEM IN THE FALL
- 5. PLUMBING DEPARTMENT REQUIRES A YEARLY SERICE TEST ON THE BACKFLOW EQUIPMENT BY CERIFIED BACKFLOW TESTER.
- 6. THE BACKFLOW ASSEMBLY IS REQUIRED TOBE INSTALLED BY A CERTIFIED PLUMBER AND APPROVED BY PLUMBING DEPT.
- 7. ALL FLANGES ARE BRASS.
- 8. COLOUR OF CABINET TO BE DETERMINED BY TOWN.



# ABOVE-GRADE METER BOX

STANDARD	DETAIL
APPROVED COUNCIL	DWG. No.
REVISION No.	705
DATE 2009	

